

#### St. Anthony Falls I-35W Bridge Replacement

#### ASHE National Conference June 13, 2014

## Dustin Thomas, P.E. I-35W Bridge Construction Engineer



## The Former Bridge - 9340

• Opened to traffic in 1967

ANTHONY FALLS

- Steel truss bridge design
- Fracture critical bridge
  - If certain components fail, bridge can fail
- Bridge and Roadway Repair Project Underway at time of collapse








#### The Collapse



- Bridge Collapsed at 6:05 p.m. Wednesday, August 1, 2007
  - Plunged nearly
    100 vehicles into
    the Mississippi
    River
    - 13 fatalities
    - 145 injuries











- 1 3/8" thick gusset plate (100 ksi)  $\rightarrow$  2 of 29 gusset plates
- 1" thick gusset plate (50 ksi)  $\rightarrow$  13 of 29 gusset plates
- 5/8" thick gusset plate (50 ksi)  $\rightarrow$  4 of 29 gusset plates
  - 1/2" thick gusset plate (50 ksi)  $\rightarrow$  10 of 29 gusset plates













# **NTSB Findings**

- Collapse resulted due to inadequate load capacity of U10 gusset plates
- The design error was not initially detected during reviews by the design consultant
- The design error remained undetected through subsequent load ratings and through annual bridge inspections.



ST. ANTHONY FALLS

## **Need for Accelerated Delivery**

- 141,000 cars a day used the bridge
  - One of the busiest bridges in the state
- Close to major traffic areas
  - U of M
  - Downtown Minneapolis
- \$400K a day in road users costs
- \$113,000 a day in economic impacts



UNIVERSITY OF MINNESOTA

win Cities . Duluth . Morris . Crookston . Rochester . Other Loca



ST. ANTHONY FALLS

## New St. Anthony Falls Bridge

#### **GOALS**

- Safety
- Quality
- Aesthetics
- Public Relations
- Enhancements
- Environmental Compliance
- Time and Budget





# **Evaluation Criteria**

- Quality (50 percent)
  - Key individuals
  - Quality Control / Quality Assurance
  - Safety

ST. ANTHONY FALLS

- Performance in construction
- Aesthetics/Visual Quality (20 percent)
  - Visual Enhancements
  - Public Involvement
- Enhancements (15 percent)
  - Roadway
  - Structural
- Public Outreach/Involvement (15 percent)
  - Impacts to the public
  - Approach to communications



ST. ANTHONY FALLS

## **Best Value Selection Process**

- Formula:
  - (Cost + (Time in days \* \$200,000))/Technical Score
  - Allowable Timeframes 337 to 437 Calendar Days

#### Best-Value = Flatiron/Manson

- 91.47 technical score \$233.8 million cost
- 437 days to complete
- Other Proposals
  - Costs Ranged From \$177 to \$219 Million
  - Days Ranged From 367 to 437



#### **Procurement Timeline**

August 1 – Collapse Occurs

ST. ANTHONY FALLS

- August 4 Issue Request for Qualifications
- August 8 Short Listed Teams
- August 23 Request For Proposals Released
- September 14 Technical Proposals Received
- September 18 Financial Proposals Received
- September 19 Project Letting
- September 20 City of Minneapolis Grants Municipal Consent
- November 15 Construction Began






# **Bridge Description**

- •Four-span bridge approximately 1225' in length
- •Concrete piers supported by footings and drilled shafts socketed into rock
- •Cast-in-Place approach spans and Precast Segmental river span (120 segments)
- •Variable depth superstructure 25' to 11'

ST. ANTHONY FALLS

•17 million pounds of rebar, 740 miles of strand, 50,000 c.y.of concrete






•Two parallel bridges, each with two box girders

•Striped for 5 lanes each direction (10 total) with 13' and 14' shoulders (actual design loading considers for 7 lanes each direction)

•Future configuration of 4 lanes each direction plus light rail line or bus transit lane (lane drop for ramps)





# **100 Year Design Life**

- •Include corrosion resistant design details with post-tensioning
- •Utilize high performance materials
- •Provide multiple layers of protection of key structural elements
- •Provide high quality construction




#### **Public Input in Design**

• Pier Shape

ST. ANTHONY FALLS


- Color of Bridge
- Native Stone Abutments












Sidewalk Talks every Saturday

More than 400 people attended on July 5, 2008



Signs mounted on 10th Avenue Bridge for self-guided tours ST. ANTHONY FALLS


## **Project Site Challenges**

- Utility Coordination
- R/W Acquisition (13 Parcels)
- Demolition Contract
- Limited Soil Investigation
- Railroad Coordination
- Hydraulic Scour
- Contaminated Materials
- Environmental Permitting (10)









#### Substructures

ST. ANTHONY FALLS



#### **Drilled Shaft Construction**

Pier #3



## **Drilled Shaft Foundations**



## 90' Average Length Socketed into Rock







## **Footing Construction**







25

ST. ANTHONY FALLS



35W

### **Pier Construction**





35W ST. ANTHONY FALLS BRIDGE REPLACEMENT

### **Pier Construction**








# Safety Management

- Partnership
  - Mn/DOT
  - Flatiron-Manson
  - Mn/OSHA
- Training of all workers assigned to project
  - Required escorts for visitors
- Large Safety Team
- Audits performed weekly
- Consistency from Top to Bottom










## Falsework









#### South side falsework

Apr. 1, 2008






#### Cast Superstructure Spans 1,3 & 4

# **High Performance Concrete**

- Performance Specifications
  - Impacts on Schedule and Quality
  - Strength, Permeability, Chloride resistance
    - Slag, Fly ash, Micro Silica
- Self Consolidating Concrete
  - Primarily used for drilled shafts
  - Volumetric Modifying Agents (VMA)
    - Helped prevent segregation in mix
- Contractor and Supplier Innovation
  - Solved past performance issues
  - Composite Gradations
    - Paving Mix includes incentives for well graded
  - Developed mix designs
    - 45 mix designs
    - Ex: 365 lbs slag, 98 lbs fly ash, 82 lbs portland
    - Silica Fume in Superstructure (approx. 3% by vol)
    - Used high range water reducing agents and retarders
    - Multiple test pours and mock ups
















Elevation of Long-Line precasting system

Precast Span 2 Segments Off-Site Pha


Phase 7

35W ST. ANTHONY FALLS BRIDGE REPLACEMENT

# **Casting Yard**




OF TRAT













#### Pre-cast segment work

Pouring top slab, road bed, first segment, Feb. 19, 2008







35W

## **Lifting Segments**








#### **Transporting Segments**













#### Erect Cantilevered Main-Span Phase 10



















## **Post-Tensioning Bars**







# **Post-Tensioning Tendons**






35W ST. ANTHONY FALLS BRIDGE REPLACEMENT





35W

### **Closure Pours**
















# "Smart Bridge" System


Integrated Bridge Sensor Monitoring System covering five areas:

- Support construction processes
- Record of structural behavior (structure monitoring)
- Control of the automated anti-icing system
- Intelligent Transportation System (ITS)
- Bridge security





- •Vibrating Wire Strain Gauge with Temperature Reading
- Linear Potentiometer
- •Accelerometer
- Corrosion Potential Sensor





## **Load Calibration of Sensors**



#### 8 Trucks @ 25 Tons Each



### **Aesthetic Lighting**



ANESOTA







#### Monuments









Ş	SCHEDULE	
(DAYS FROM NTP - C	OCTOBER	8, 2007)
ACTIVITY		DAY
DRILLED SHAFTS	-	50
FOOTING	-	92
PIERS	-	100
PRECASTING	-	107
CIP SPAN	-	170
PRECAST ERECTION	I –	223
ERECTION COMPLET	ΓED -	269
OPENING (SEPT. 18)	-	339
SUBSTANTIAL COMP	L	346

#### COMPLETED IN 11 MONTHS OPENED OVER 3 MONTHS AHEAD OF SCHEDULE



THE CONSTRUCTION WEEKLY

**Engineering News-Record** 

Tragedy becomes triumph in swift rebuilding of I-35W bridg September 15, 2008 + enr.com

Odds improve Storms show for \$8-billion weakness of

trust-fund fix power grid

Disconnected

Louisiana

Rescue

highway

**Minneapolis Marvel** 

The McGrane Hill Companie


proposes

tough new

crane rules

Action Maryland

#### **ST ANTHONY FALLS** Open to Traffic September 19, 2008



Completed in 11 Months – 3 Months Early





#### Schedule and Budget

- Schedule
  - Contract Completion Date: December 24, 2008
  - Open to Traffic: September 18, 2008
  - Substantial Completion Reached 90 days ahead of schedule
- Budget
  - Little cost growth (1% +-)
- Incentives
  - \$18 million in time
  - \$7 million No-Excuse Bonus



## **35W Innovation**

- High Performance Concrete
- Mass Concrete

- Self-consolidating concrete
- Cold Weather Protection
- Involvement of Engineer of Record
- LED Lighting
- Smart Bridge Technology



# **35W Keys to Success**

- Approach to Safety
- Approach to Quality
  - Involvement of Engineer of Record in Construction
- Innovation

- Partnership
- Communication
- History of Working Together
  - Flatiron and Figg Engineering
  - Mn/DOT Team
- Risk Management
  - Who can best manage the risk



